BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54281

APPROVED SCHEDULE - B

NO.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Supply and installation of CCTV cameras at selected points in ward no 12 - Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARSIMHA K (SREE VIGNESHWARA ENTERPRISES)	
				In Figures	In Words
1	16.00	Supplying ,Installartion,Commisoning and Testing CP Plus 3MP ,Meters ip bullet camera,1/3" 3MP PS CMOS image sensor 25fps@3MP ,25/30fps@1080P , H.264,H.264H ,H.264B,MJPEG dual- codec encording DWDR configure(CR) 3DNR,ROI , AWB AGC,BLC , HLC 3.6mm fixed lens (6mm optional),IR Range of 50Mtr IP67 6' , perd,PoE Mobile software iCMOB, CMS Software :KVMS Pro ,vOptimus Pro inclusive of all Taxes , transportation charges as per the direction of Engineer incharge .	No	18614.62	Rupees Eighteen Thousand Six Hundred Fourteen and Sixty Two Paise Only
2	1.00	Supplying ,Installation,Commisioning and Testing CP PLUS 32 Ch.H.265,4K Network Vedeo Recorder Up to 32 channel IP Camera,input H265/H 264 dual codec decording up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth support 4SATA HDDs upto 24 TB ,2USB(1USB3.0)HDMI/VGA simaltaneous vedeooutpu support multy band network cameras ONVIF Version 2.4 conformance mobile software iCMOB ,gCMOB inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	55349.28	Rupees Fifty Five Thousand Three Hundred Forty Nine and Twenty Eight Paise Only
3	1.00	Supplying ,Installation,Commisioning and Testing Netgear Ready NAS 4bay Diskless Network Attached Storage for personal Cloud by Netgear inclusive of all taxes transportation charges as per the direction of Engineer incharge	No	215392.80	Rupees Two Hundred Fifteen Thousand Three Hundred Ninety Two and Eighty Paise Only
4	1.00	Providing and supplying NAS Hard disk 6 TB inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	20034.00	Rupees Twenty Thousand Thirty Four Only
5	1.00	Supplying ,Installation,Commisioning and Testing D-Link 24-Port Gigabite Switch with 4 combo SFP Ports inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	28812.00	Rupees Twenty Eight Thousand Eight Hundred Twelve Only
6	1.00	Supplying ,Installation,Commisioning and Testing D-Link 8-Port Gigabite Switch with 2 combo SFP Ports inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	23100.00	Rupees Twenty Three Thousand One Hundred Only
7	7.00	Providing and supplying CATS out door-305 Mtr cable Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	53130.00	Rupees Fifty Three Thousand One Hundred Thirty Only
8	1.00	Providing and fixing Media converter Giga Dlink inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	9408.00	Rupees Nine Thousand Four Hundred Eight Only
9	8.00	Providing Cctv MS poles with camera fixing brackets 5 to 6 Mtr Height Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	19740.00	Rupees Nineteen Thousand Seven Hundred Forty Only
10	8.00	Providing and fixing MS Boxes to poles with rust proof powder coating Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	7140.00	Rupees Seven Thousand One Hundred Forty Only
11	8.00	Providing and fixing electrical works for Boxes for power supply PVC Boards with three pin sockets and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer incharge	No	6300.00	Rupees Six Thousand Three Hundred Only
12	12.00	Providing Internet charges connecting CCTV with IP Based for one month	No	2520.00	Rupees Two Thousand Five Hundred Twenty Only
13	3.00	Providing and fixing SFP-LX-SM GIGA Module Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	5040.00	Rupees Five Thousand Forty Only
14	3.00	Providing and fixing fiber optic PATCH Chords Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	1848.00	Rupees One Thousand Eight Hundred Forty Eight Only
15	2.00	Supplying ,Installation,Commisioning and Testing UPS 2 KVA with 2 Bateries Box inclusive all taxes transportation charges as per the direction of Engineer incharge .	No	54096.00	Rupees Fifty Four Thousand Ninety Six Only

K. Narasimha

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARSIMHA K (SREE VIGNESHWARA ENTERPRISES)	
				In Figures	In Words
16	8.00	Erecting of pole ,The pole shall be erected and cement concrete work (1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be upto 0.6Mtrabove ground level as per IS 2713-7.1 Erection of light duty pole on footpath 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer incharge .	No	5292.00	Rupees Five Thousand Two Hundred Ninety Two Only
17	16.00	Providing and fixing HDMI cables 10Mtrs inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	5210.00	Rupees Five Thousand Two Hundred Ten Only
18	3.00	Supplying ,Installation,Commisioning and Testing Vedeo Manager Application Software Manager for display and Management of Camera on vedeo display Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	28140.00	Rupees Twenty Eight Thousand One Hundred Forty Only
19	4.00	Supplying ,Installation,Commisioning and Testing server rack 15u box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	28980.00	Rupees Twenty Eight Thousand Nine Hundred Eighty Only

R. Narasimha.

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92